

VILLAGE OF LIBERTYVILLE

Nicholas Dowden Park FLOOD CONTROL PROJECT - PHASE 1

Bid Tab

Christopher B. Burke Engineering, Ltd.

9575 West Higgins Road, Suite 600

Rosemont, Illinois 60018

(CBBEL Project No. 20-0140)

DATE: June 17, 2022

CODE	ITEMS	UNIT	QUANTITY	ENGINEER'S ESTIMATE		Campanella & Sons, Inc.		Berger Excavating		V3 Construction Group, Ltd.	
				UNIT PRICE	TOTAL COST	UNIT PRICE	TOTAL COST	UNIT PRICE	TOTAL COST	UNIT PRICE	TOTAL COST
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	275	\$35.00	\$9,625.00	\$12.10	\$3,327.50	\$11.00	\$3,025.00	\$12.00	\$3,300.00
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	800	\$45.00	\$36,000.00	\$19.80	\$15,840.00	\$18.00	\$14,400.00	\$19.00	\$15,200.00
*20101200	TREE ROOT PRUNING	EACH	20	\$200.00	\$4,000.00	\$99.00	\$1,980.00	\$90.00	\$1,800.00	\$95.00	\$1,900.00
20200100	EARTH EXCAVATION (BASIN)	CU YD	71,500	\$40.00	\$2,860,000.00	\$30.57	\$2,185,755.00	\$32.70	\$2,338,050.00	\$32.65	\$2,334,475.00
20200100	EARTH EXCAVATION (PARKING STALLS)	CU YD	400	\$50.00	\$20,000.00	\$57.00	\$22,800.00	\$50.00	\$20,000.00	\$35.00	\$14,000.00
20200100	EARTH EXCAVATION (NORTHERN SWALE)	CU YD	350	\$50.00	\$17,500.00	\$57.00	\$19,950.00	\$53.00	\$18,550.00	\$38.00	\$13,300.00
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (TOPSOIL DISPOSAL)	CU YD	1,000	\$50.00	\$50,000.00	\$38.35	\$38,350.00	\$46.00	\$46,000.00	\$30.00	\$30,000.00
*20800150	TRENCH BACKFILL, SPECIAL (STORM SEWER)	CU YD	400	\$45.00	\$18,000.00	\$73.04	\$29,216.00	\$60.00	\$24,000.00	\$93.00	\$37,200.00
21101505	TOPSOIL EXCAVATION AND PLACEMENT (12")	CU YD	16,500	\$12.50	\$206,250.00	\$15.91	\$262,515.00	\$10.10	\$166,650.00	\$14.00	\$231,000.00
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	1,500	\$5.00	\$7,500.00	\$7.15	\$10,725.00	\$6.00	\$9,000.00	\$6.25	\$9,375.00
25000100	SEEDING, CLASS 1	SQ YD	33,000	\$3.00	\$99,000.00	\$0.79	\$26,070.00	\$1.95	\$64,350.00	\$1.25	\$41,250.00
25100630	EROSION CONTROL BLANKET	SQ YD	47,500	\$3.00	\$142,500.00	\$1.10	\$52,250.00	\$1.15	\$54,625.00	\$1.25	\$59,375.00
*25200200	SUPPLEMENTAL WATERING	UNIT	1,000	\$100.00	\$100,000.00	\$11.00	\$11,000.00	\$50.00	\$50,000.00	\$53.00	\$53,000.00
28000400	PERIMETER EROSION BARRIER	FOOT	4,250	\$5.00	\$21,250.00	\$2.75	\$11,687.50	\$3.40	\$14,450.00	\$2.50	\$10,625.00
*28000500	CULVERT INLET PROTECTION	EACH	8	\$250.00	\$2,000.00	\$330.00	\$2,640.00	\$265.00	\$2,120.00	\$420.00	\$3,360.00
*28000510	INLET FILTERS	EACH	15	\$150.00	\$2,250.00	\$220.00	\$3,300.00	\$265.00	\$3,975.00	\$320.00	\$4,800.00
28100107	STONE RIPRAP, RR-4	SQ YD	500	\$20.00	\$10,000.00	\$126.62	\$63,310.00	\$98.00	\$49,000.00	\$91.00	\$45,500.00
28200200	FILTER FABRIC	SQ YD	500	\$10.00	\$5,000.00	\$3.75	\$1,875.00	\$6.00	\$3,000.00	\$5.50	\$2,750.00
35102400	AGGREGATE BASE COURSE, TYPE B 12"	SQ YD	900	\$15.00	\$13,500.00	\$29.06	\$26,154.00	\$22.25	\$20,025.00	\$23.00	\$20,700.00
40300200	BITUMINOUS MATERIALS (PRIME COAT)	POUND	1,000	\$1.00	\$1,000.00	\$0.01	\$10.00	\$0.01	\$10.00	\$0.10	\$100.00
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	175	\$95.00	\$16,625.00	\$130.90	\$22,907.50	\$119.00	\$20,825.00	\$120.00	\$21,000.00
40604060	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N50	TON	125	\$100.00	\$12,500.00	\$137.50	\$17,187.50	\$125.00	\$15,625.00	\$130.00	\$16,250.00
*42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH (SPECIAL)	SQ FT	1,500	\$8.00	\$12,000.00	\$11.32	\$16,980.00	\$10.34	\$15,510.00	\$12.00	\$18,000.00
*42400800	DETECTABLE WARNINGS	SQ FT	50	\$50.00	\$2,500.00	\$82.50	\$4,125.00	\$39.00	\$1,950.00	\$41.00	\$2,050.00
*44000100	PAVEMENT REMOVAL	SQ YD	1,400	\$10.00	\$14,000.00	\$16.84	\$23,576.00	\$14.00	\$19,600.00	\$12.00	\$16,800.00
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	50	\$20.00	\$1,000.00	\$18.71	\$935.50	\$14.00	\$700.00	\$21.00	\$1,050.00
44000600	SIDEWALK REMOVAL	SQ FT	4,000	\$3.00	\$12,000.00	\$1.29	\$5,160.00	\$1.15	\$4,600.00	\$2.50	\$10,000.00
*44201723	CLASS D PATCHES, 6" (SPECIAL)	SQ YD	250	\$60.00	\$15,000.00	\$105.60	\$26,400.00	\$108.00	\$27,000.00	\$100.00	\$25,000.00
50105220	PIPE CULVERT REMOVAL	FOOT	20	\$20.00	\$400.00	\$56.13	\$1,122.60	\$32.00	\$640.00	\$14.00	\$280.00
52200800	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	600	\$75.00	\$45,000.00	\$66.78	\$40,068.00	\$54.00	\$32,400.00	\$53.00	\$31,800.00
*54001002	BOX CULVERT END SECTIONS, CULVERT NO. 2 (8'x3' RCBC) W/ GRATE	EACH	1	\$10,000.00	\$10,000.00	\$21,014.87	\$21,014.87	\$26,000.00	\$26,000.00	\$39,900.00	\$39,900.00
54010604	PRECAST CONCRETE BOX CULVERTS, 8'x3'	FOOT	100	\$1,250.00	\$125,000.00	\$1,088.91	\$108,891.00	\$1,265.00	\$126,500.00	\$1,500.00	\$150,000.00
*54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18" W/ GRATE	EACH	1	\$4,000.00	\$4,000.00	\$2,636.57	\$2,636.57	\$2,000.00	\$2,000.00	\$3,100.00	\$3,100.00
*54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24" W/ GRATE	EACH	1	\$4,500.00	\$4,500.00	\$3,278.28	\$3,278.28	\$2,500.00	\$2,500.00	\$3,300.00	\$3,300.00
*54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30" W/ GRATE	EACH	4	\$5,500.00	\$22,000.00	\$4,177.36	\$16,709.44	\$7,500.00	\$30,000.00	\$3,300.00	\$13,200.00
*54214509	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24" W/ GRATE	EACH	1	\$6,500.00	\$6,500.00	\$5,705.01	\$5,705.01	\$3,950.00	\$3,950.00	\$3,700.00	\$3,700.00
550A0140	STORM SEWERS, CLASS A, TYPE 1, 30"	FOOT	20	\$200.00	\$4,000.00	\$268.28	\$5,365.60	\$125.00	\$2,500.00	\$300.00	\$6,000.00
550A0340	STORM SEWERS, CLASS A, TYPE 2, 12"	FOOT	50	\$125.00	\$6,250.00	\$106.84	\$5,342.00	\$65.00	\$3,250.00	\$220.00	\$11,000.00
550A0380	STORM SEWERS, CLASS A, TYPE 2, 18"	FOOT	20	\$130.00	\$2,600.00	\$182.08	\$3,641.60	\$78.00	\$1,560.00	\$260.00	\$5,200.00
550A0410	STORM SEWERS, CLASS A, TYPE 2, 24"	FOOT	80	\$125.00	\$10,000.00	\$163.44	\$13,075.20	\$150.00	\$12,000.00	\$230.00	\$18,400.00
550A0430	STORM SEWERS, CLASS A, TYPE 2, 30"	FOOT	525	\$150.00	\$78,750.00	\$146.04	\$76,771.00	\$126.00	\$66,150.00	\$280.00	\$147,000.00
550A0480	STORM SEWERS, CLASS A, TYPE 2, 48"	FOOT	15	\$300.00	\$4,500.00	\$522.14	\$7,832.10	\$266.00	\$3,990.00	\$420.00	\$6,300.00
540A900	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 24"	FOOT	100	\$750.00	\$75,000.00	\$262.26	\$26,226.00	\$270.00	\$27,000.00	\$330.00	\$33,000.00
*550B0040	STORM SEWERS, CLASS B, TYPE 1 6"	FOOT	300	\$50.00	\$15,000.00	\$51.34	\$15,402.00	\$54.50	\$16,350.00	\$39.00	\$11,700.00
*550B0330	STORM SEWERS, CLASS B, TYPE 2 6"	FOOT	250	\$60.00	\$15,000.00	\$57.91	\$14,477.50	\$56.00	\$14,000.00	\$43.00	\$10,750.00
*550B0360	STORM SEWERS, CLASS B, TYPE 2 15"	FOOT	20	\$75.00	\$1,500.00	\$221.96	\$4,439.20	\$140.00	\$2,800.00	\$120.00	\$2,400.00
*55100100	STORM SEWER REMOVAL 4"	FOOT	25	\$10.00	\$250.00	\$23.00	\$575.00	\$18.00	\$450.00	\$11.00	\$275.00
*55100200	STORM SEWER REMOVAL 6"	FOOT	250	\$10.00	\$2,500.00	\$24.93	\$6,232.50	\$18.00	\$4,500.00	\$11.00	\$2,750.00

				ENGINEER'S ESTIMATE		Campanella & Sons, Inc.		Berger Excavating		V3 Construction Group, Ltd.	
*55100300	STORM SEWER REMOVAL 8"	FOOT	50	\$10.00	\$500.00	\$21.31	\$1,065.50	\$18.00	\$900.00	\$11.00	\$550.00
*55100400	STORM SEWER REMOVAL 10"	FOOT	225	\$10.00	\$2,250.00	\$24.62	\$5,539.50	\$18.00	\$4,050.00	\$12.00	\$2,700.00
*55101200	STORM SEWER REMOVAL 24"	FOOT	925	\$20.00	\$18,500.00	\$27.20	\$25,160.00	\$25.00	\$23,125.00	\$15.00	\$13,875.00
*56100600	DUCTILE IRON WATER MAIN, 6"	FOOT	50	\$125.00	\$6,250.00	\$137.62	\$6,881.00	\$155.00	\$7,750.00	\$370.00	\$18,500.00
*56100900	DUCTILE IRON WATER MAIN, 12"	FOOT	150	\$150.00	\$22,500.00	\$215.98	\$32,397.00	\$225.00	\$33,750.00	\$520.00	\$78,000.00
*56400500	FIRE HYDRANTS TO BE REMOVED	EACH	3	\$750.00	\$2,250.00	\$2,158.20	\$6,474.60	\$1,275.00	\$3,825.00	\$4,800.00	\$14,400.00
*56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	3	\$6,500.00	\$19,500.00	\$9,140.41	\$27,421.23	\$8,700.00	\$26,100.00	\$14,200.00	\$42,600.00
60108106	PIPE UNDERDRAINS, TYPE 1, 6"	FOOT	6,250	\$45.00	\$281,250.00	\$37.27	\$232,937.50	\$43.00	\$268,750.00	\$30.00	\$187,500.00
60108108	PIPE UNDERDRAINS, TYPE 1, 8"	FOOT	400	\$65.00	\$26,000.00	\$40.20	\$16,080.00	\$95.00	\$38,000.00	\$44.00	\$17,600.00
*60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	\$4,500.00	\$4,500.00	\$4,126.09	\$4,126.09	\$3,200.00	\$3,200.00	\$4,000.00	\$4,000.00
*60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	\$4,500.00	\$4,500.00	\$3,972.89	\$3,972.89	\$3,100.00	\$3,100.00	\$4,400.00	\$4,400.00
*60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	5	\$2,500.00	\$12,500.00	\$2,390.60	\$11,953.00	\$1,825.00	\$9,125.00	\$1,900.00	\$9,500.00
*60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	\$6,000.00	\$30,000.00	\$5,999.37	\$29,996.85	\$5,600.00	\$28,000.00	\$7,300.00	\$36,500.00
*60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	\$7,500.00	\$22,500.00	\$9,635.62	\$28,906.86	\$9,400.00	\$28,200.00	\$11,200.00	\$33,600.00
*60224459	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	\$9,000.00	\$9,000.00	\$24,970.08	\$24,970.08	\$17,300.00	\$17,300.00	\$20,500.00	\$20,500.00
*60234200	INLETS, TYPE A, EJ 5030 FRAME AND LID	EACH	2	\$2,500.00	\$5,000.00	\$2,189.28	\$4,378.56	\$2,500.00	\$5,000.00	\$1,900.00	\$3,800.00
*60400105	FRAMES, TYPE 1 (EJ 5050 FRAME AND LID)	EACH	1	\$500.00	\$500.00	\$1,072.07	\$1,072.07	\$1,200.00	\$1,200.00	\$690.00	\$690.00
*60603500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1,300	\$30.00	\$39,000.00	\$61.35	\$79,755.00	\$35.75	\$46,475.00	\$46.00	\$59,800.00
*66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1,000	\$100.00	\$100,000.00	\$80.00	\$80,000.00	\$0.01	\$10.00	\$78.00	\$78,000.00
*66900530	SOIL DISPOSAL ANALYSIS	EACH	5	\$2,000.00	\$10,000.00	\$1,430.00	\$7,150.00	\$1.00	\$5.00	\$1,600.00	\$8,000.00
*66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	L. SUM	1	\$5,000.00	\$5,000.00	\$3,520.00	\$3,520.00	\$1.00	\$1.00	\$1,600.00	\$1,600.00
*66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L. SUM	1	\$5,000.00	\$5,000.00	\$2,640.00	\$2,640.00	\$1.00	\$1.00	\$1,600.00	\$1,600.00
*66901006	REGULATED SUBSTANCES MONITORING	CAL DAY	10	\$500.00	\$5,000.00	\$968.00	\$9,680.00	\$1.00	\$10.00	\$1,600.00	\$16,000.00
67100100	MOBILIZATION	L. SUM	1	\$250,000.00	\$250,000.00	\$230,000.00	\$230,000.00	\$335,000.00	\$335,000.00	\$205,000.00	\$205,000.00
*70100100	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L. SUM	1	\$125,000.00	\$125,000.00	\$20,000.00	\$20,000.00	\$35,000.00	\$35,000.00	\$13,000.00	\$13,000.00
72000100	SIGN PANEL - TYPE 1	SQ FT	10	\$50.00	\$500.00	\$55.00	\$550.00	\$24.00	\$240.00	\$110.00	\$1,100.00
72900100	METAL POST - TYPE A	FOOT	30	\$50.00	\$1,500.00	\$27.50	\$825.00	\$30.00	\$900.00	\$53.00	\$1,590.00
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	50	\$10.00	\$500.00	\$38.50	\$1,925.00	\$15.00	\$750.00	\$160.00	\$8,000.00
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,250	\$4.00	\$5,000.00	\$6.05	\$7,562.50	\$2.00	\$2,500.00	\$6.00	\$7,500.00
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	150	\$6.00	\$900.00	\$9.35	\$1,402.50	\$3.00	\$450.00	\$11.00	\$1,650.00
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	175	\$8.00	\$1,400.00	\$18.70	\$3,272.50	\$6.00	\$1,050.00	\$22.00	\$3,850.00
*80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	\$1,500.00	\$1,500.00	\$4,082.24	\$4,082.24	\$2,500.00	\$2,500.00	\$14,000.00	\$14,000.00
*80400200	ELECTRIC UTILITY SERVICE CONNECTION	EACH	1	\$10,000.00	\$10,000.00	\$10,000.00	\$10,000.00	\$10,000.00	\$10,000.00	\$11,000.00	\$11,000.00
81028730	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 1 1/4" DIA.	FOOT	805	\$20.00	\$16,100.00	\$12.50	\$10,062.50	\$20.14	\$16,212.70	\$12.00	\$9,660.00
81028750	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2" DIA.	FOOT	585	\$30.00	\$17,550.00	\$21.65	\$12,665.25	\$25.19	\$14,736.15	\$16.00	\$9,360.00
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	1,395	\$2.50	\$3,487.50	\$1.67	\$2,329.65	\$2.00	\$2,790.00	\$3.00	\$4,185.00
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	1,890	\$5.00	\$9,450.00	\$2.68	\$5,065.20	\$2.60	\$4,914.00	\$4.00	\$7,560.00
81702170	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2/0	FOOT	1,785	\$7.50	\$13,387.50	\$7.48	\$13,351.80	\$7.50	\$13,387.50	\$9.00	\$16,065.00
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	6	\$250.00	\$1,500.00	\$535.11	\$3,210.66	\$1,800.00	\$10,800.00	\$650.00	\$3,900.00
84200804	REMOVAL OF POLE FOUNDATION	EACH	1	\$500.00	\$500.00	\$945.73	\$945.73	\$1,325.00	\$1,325.00	\$350.00	\$350.00
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	3	\$5,000.00	\$15,000.00	\$3,665.98	\$10,997.94	\$3,700.00	\$11,100.00	\$4,700.00	\$14,100.00
*X0320067	BENCH REMOVAL	EACH	6	\$50.00	\$300.00	\$324.43	\$1,946.58	\$450.00	\$2,700.00	\$280.00	\$1,680.00
*X0325815	REMOVE EXISTING CABLE	FOOT	200	\$5.00	\$1,000.00	\$2.46	\$492.00	\$10.00	\$2,000.00	\$2.75	\$550.00
*X0322881	TREE TRIMMING	EACH	10	\$250.00	\$2,500.00	\$99.00	\$990.00	\$90.00	\$900.00	\$95.00	\$950.00
*X0426200	DEWATERING	L. SUM	1	\$100,000.00	\$100,000.00	\$23,195.82	\$23,195.82	\$22,000.00	\$22,000.00	\$7,900.00	\$7,900.00
*X1200043	PRECAST CONCRETE JUNCTION CHAMBER, 10'x12'	EACH	1	\$75,000.00	\$75,000.00	\$74,645.01	\$74,645.01	\$78,500.00	\$78,500.00	\$84,500.00	\$84,500.00
*X1400088	POWER PEDESTAL	EACH	2	\$5,000.00	\$10,000.00	\$3,568.90	\$7,137.80	\$6,000.00	\$12,000.00	\$2,700.00	\$5,400.00
*X1400395	LIGHTING PANELBOARD	EACH	1	\$5,000.00	\$5,000.00	\$6,919.06	\$6,919.06	\$1,000.00	\$1,000.00	\$530.00	\$530.00
*X5610004	DUCTILE IRON WATER MAIN FITTINGS	POUND	1,500	\$5.00	\$7,500.00	\$13.25	\$19,875.00	\$9.00	\$13,500.00	\$7.75	\$11,625.00
*X5610704	WATER MAIN REMOVAL, 4"	FOOT	50	\$20.00	\$1,000.00	\$62.04	\$3,102.00	\$45.00	\$2,250.00	\$180.00	\$9,000.00
*X5610712	WATER MAIN REMOVAL, 12"	FOOT	125	\$20.00	\$2,500.00	\$51.19	\$6,398.75	\$45.00	\$5,625.00	\$220.00	\$27,500.00
*X8100105	CONDUIT SPLICE	EACH	1	\$500.00	\$500.00	\$593.70	\$593.70	\$3,500.00	\$3,500.00	\$320.00	\$320.00
*Z0013798	CONSTRUCTION LAYOUT	L. SUM	1	\$50,000.00	\$50,000.00	\$60,000.00	\$60,000.00	\$28,200.00	\$28,200.00	\$45,200.00	\$45,200.00
*Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	6	\$500.00	\$3,000.00	\$382.84	\$2,297.04	\$700.00	\$4,200.00	\$1,100.00	\$6,600.00
*Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	14	\$750.00	\$10,500.00	\$736.33	\$10,308.62	\$540.00	\$7,560.00	\$260.00	\$3,640.00
*Z0022800	FENCE REMOVAL	FOOT	650	\$10.00	\$6,500.00	\$11.88	\$7,722.00	\$8.00	\$5,200.00	\$11.00	\$7,150.00
*Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	350	\$25.00	\$8,750.00	\$41.04	\$14,364.00	\$50.50	\$17,675.00	\$300.00	\$105,000.00
*Z0004510	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"	SQ YD	50	\$50.00	\$2,500.00	\$119.34	\$5,967.00	\$63.00	\$3,150.00	\$66.00	\$3,300.00

				ENGINEER'S ESTIMATE		Campanella & Sons, Inc.		Berger Excavating		V3 Construction Group, Ltd.	
*Z0033024	MAINTAIN EXISTING LIGHTING SYSTEM	L. SUM	1	\$2,500.00	\$2,500.00	\$4,910.30	\$4,910.30	\$3,000.00	\$3,000.00	\$11,000.00	\$11,000.00
*Z0055905	TEMPORARY CONSTRUCTION FENCE, 6'	FOOT	3,250	\$20.00	\$65,000.00	\$11.00	\$35,750.00	\$12.00	\$39,000.00	\$9.00	\$29,250.00
*Z0056668	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 12"	FOOT	225	\$150.00	\$33,750.00	\$135.77	\$30,548.25	\$125.00	\$28,125.00	\$170.00	\$38,250.00
*Z0056668	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 12"	FOOT	25	\$200.00	\$5,000.00	\$213.27	\$5,331.75	\$151.00	\$3,775.00	\$320.00	\$8,000.00
*Z0056672	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 24"	FOOT	125	\$175.00	\$21,875.00	\$348.72	\$43,590.00	\$300.00	\$37,500.00	\$340.00	\$42,500.00
*NA	CLEANOUT, 6"	EACH	42	\$900.00	\$37,800.00	\$1,124.28	\$47,219.76	\$550.00	\$23,100.00	\$910.00	\$38,220.00
*NA	CONTINGENCY - EARTHWORK	DOLLAR	25,000	\$1.00	\$25,000.00	\$1.00	\$25,000.00	\$1.00	\$25,000.00	\$1.00	\$25,000.00
*NA	CONTINGENCY - LANDSCAPING	DOLLAR	25,000	\$1.00	\$25,000.00	\$1.00	\$25,000.00	\$1.00	\$25,000.00	\$1.00	\$25,000.00
*NA	CONTINGENCY - PARK AMENITIES	DOLLAR	25,000	\$1.00	\$25,000.00	\$1.00	\$25,000.00	\$1.00	\$25,000.00	\$1.00	\$25,000.00
*NA	CONTINGENCY - PAVING	DOLLAR	25,000	\$1.00	\$25,000.00	\$1.00	\$25,000.00	\$1.00	\$25,000.00	\$1.00	\$25,000.00
*NA	CONTINGENCY - UTILITIES	DOLLAR	75,000	\$1.00	\$75,000.00	\$1.00	\$75,000.00	\$1.00	\$75,000.00	\$1.00	\$75,000.00
*NA	FIELD OF DREAMS SEED MIX	SQ YD	13,000	\$3.00	\$39,000.00	\$0.83	\$10,790.00	\$2.45	\$31,850.00	\$6.00	\$78,000.00
*NA	ICE RINK COPPER DRAIN PIPE AND VALVE	L. SUM	1	\$20,000.00	\$20,000.00	\$21,682.55	\$21,682.55	\$29,500.00	\$29,500.00	\$15,800.00	\$15,800.00
*NA	INLINE CHECK VALVE, 6"	EACH	9	\$5,000.00	\$45,000.00	\$1,520.38	\$13,683.42	\$1,900.00	\$17,100.00	\$2,600.00	\$23,400.00
*NA	INLINE CHECK VALVE, 18"	EACH	1	\$10,000.00	\$10,000.00	\$6,486.45	\$6,486.45	\$7,500.00	\$7,500.00	\$10,100.00	\$10,100.00
*NA	IRRIGATION SYSTEM, COMPLETE	L. SUM	1	\$75,000.00	\$75,000.00	\$58,850.00	\$58,850.00	\$68,050.00	\$68,050.00	\$50,300.00	\$50,300.00
*NA	LOCATING UNDERGROUND UTILITY	EACH	5	\$2,000.00	\$10,000.00	\$890.66	\$4,453.30	\$700.00	\$3,500.00	\$1,500.00	\$7,500.00
*NA	REINFORCED CONCRETE BOX CULVERT ELBOW 8'x3', 58-DEGREE BEND	EACH	1	\$10,000.00	\$10,000.00	\$11,388.91	\$11,388.91	\$15,000.00	\$15,000.00	\$18,300.00	\$18,300.00
*NA	SAND CHANNEL DRAINAGE	SQ FT	4,000	\$5.00	\$20,000.00	\$19.61	\$78,440.00	\$0.01	\$40.00	\$23.00	\$92,000.00
*NA	SKATING RINK LINER	SQ FT	19,500	\$1.50	\$29,250.00	\$2.33	\$45,435.00	\$2.60	\$50,700.00	\$2.25	\$43,875.00
*NA	STORAGE BUILDING ELECTRICAL WORK	L. SUM	1	\$10,000.00	\$10,000.00	\$21,147.75	\$21,147.75	\$16,500.00	\$16,500.00	\$23,900.00	\$23,900.00
*NA	TEMPORARY CONSTRUCTION FENCE FOR TREE PROTECTION	FOOT	1,500	\$5.00	\$7,500.00	\$8.80	\$13,200.00	\$5.00	\$7,500.00	\$7.25	\$10,875.00
*NA	WATER MAIN CONNECTION TO EXISTING WATER MAIN (NON-PRESSURE) - DISCONNECT AND CAP	EACH	2	\$6,000.00	\$12,000.00	\$3,642.48	\$7,284.96	\$8,500.00	\$17,000.00	\$14,700.00	\$29,400.00
*NA	BACKSTOP FENCE, 24FT HT	FOOT	240	\$540.00	\$129,600.00	\$588.50	\$141,240.00	\$487.50	\$117,000.00	\$420.00	\$100,800.00
*NA	CHAIN LINK FENCE, COATED, 10FT HT	FOOT	320	\$125.00	\$40,000.00	\$143.00	\$45,760.00	\$167.00	\$53,440.00	\$160.00	\$51,200.00
*NA	CHAIN LINK FENCE, COATED, 8FT HT	FOOT	240	\$100.00	\$24,000.00	\$132.00	\$31,680.00	\$183.50	\$44,040.00	\$150.00	\$36,000.00
*NA	CHAIN LINK FENCE, COATED, 6FT HT	FOOT	256	\$75.00	\$19,200.00	\$96.25	\$24,640.00	\$99.00	\$25,344.00	\$120.00	\$30,720.00
*NA	DUGOUT STRUCTURE (PURCHASE)	EACH	8	\$12,000.00	\$96,000.00	\$14,819.08	\$118,552.64	\$13,700.00	\$109,600.00	\$13,400.00	\$107,200.00
*NA	DUGOUT STRUCTURE (INSTALLATION)	EACH	8	\$6,000.00	\$48,000.00	\$8,703.75	\$69,630.00	\$8,900.00	\$71,200.00	\$4,600.00	\$36,800.00
*NA	DUGOUT FOOTINGS	CU YD	30	\$900.00	\$27,000.00	\$681.78	\$20,453.40	\$1,117.21	\$33,516.30	\$2,100.00	\$63,000.00
*NA	STORAGE STRUCTURE (PURCHASE)	L. SUM	1	\$112,000.00	\$112,000.00	\$207,329.07	\$207,329.07	\$180,000.00	\$180,000.00	\$177,600.00	\$177,600.00
*NA	STORAGE STRUCTURE (INSTALLATION)	L. SUM	1	\$84,000.00	\$84,000.00	\$181,390.00	\$181,390.00	\$142,650.00	\$142,650.00	\$53,500.00	\$53,500.00
*NA	BUILDING FOUNDATION	CU YD	16	\$900.00	\$14,400.00	\$1,434.25	\$22,948.00	\$2,025.00	\$32,400.00	\$2,100.00	\$33,600.00
*NA	BUILDING SLAB W/ WWF	SQ FT	832	\$12.00	\$9,984.00	\$11.00	\$9,152.00	\$20.15	\$16,764.80	\$31.00	\$25,792.00
*NA	PLAYER BENCHES	EACH	8	\$1,000.00	\$8,000.00	\$2,485.63	\$19,885.04	\$4,150.00	\$33,200.00	\$1,300.00	\$10,400.00
*NA	CLAY INFIELD, 6IN DEPTH	CU YD	685	\$40.00	\$27,400.00	\$122.19	\$83,700.15	\$215.00	\$147,275.00	\$99.00	\$67,815.00
*NA	BASES, HOME PLATE, PITCHING PLATE (SET)	EACH	4	\$1,000.00	\$4,000.00	\$6,342.31	\$25,369.24	\$5,300.00	\$21,200.00	\$1,400.00	\$5,600.00
*NA	CLAY BRICKS	SQ FT	230	\$18.00	\$4,140.00	\$27.50	\$6,325.00	\$86.00	\$19,780.00	\$59.00	\$13,570.00
*NA	SOD FOR UNDERDRAIN	SQ FT	1,110	\$11.00	\$12,210.00	\$3.03	\$3,363.30	\$2.00	\$2,220.00	\$2.50	\$2,775.00
*NA	LIMESTONE PAVING	SQ FT	2,025	\$4.00	\$8,100.00	\$5.57	\$11,279.25	\$4.25	\$8,606.25	\$19.00	\$38,475.00
*NA	STEEL EDGING	FOOT	160	\$8.00	\$1,280.00	\$22.00	\$3,520.00	\$36.00	\$5,760.00	\$120.00	\$19,200.00
*NA	DOUBLE BATTING CAGE AND NETTING (PURCHASE)	EACH	1	\$12,000.00	\$12,000.00	\$15,746.95	\$15,746.95	\$16,500.00	\$16,500.00	\$13,500.00	\$13,500.00
*NA	DOUBLE BATTING CAGE AND NETTING (INSTALLATION)	EACH	1	\$6,000.00	\$6,000.00	\$18,404.10	\$18,404.10	\$22,100.00	\$22,100.00	\$11,360.00	\$11,360.00
*NA	CONCRETE PAVING	SQ FT	12,365	\$10.00	\$123,650.00	\$12.16	\$150,358.40	\$10.61	\$131,192.65	\$13.00	\$160,745.00
*NA	ASPHALT PAVING	SQ YD	470	\$32.00	\$15,040.00	\$64.23	\$30,188.10	\$65.50	\$30,785.00	\$47.00	\$22,090.00
*NA	PLANTING SOIL, 12IN DEPTH	CU YD	44	\$75.00	\$3,300.00	\$84.70	\$3,726.80	\$140.00	\$6,160.00	\$95.00	\$4,180.00
*NA	MULCH, 3IN DEPTH	CU YD	11	\$45.00	\$495.00	\$99.00	\$1,089.00	\$75.00	\$825.00	\$85.00	\$935.00
*NA	TREES	EACH	4	\$600.00	\$2,400.00	\$770.00	\$3,080.00	\$600.00	\$2,400.00	\$650.00	\$2,600.00
*NA	SMALL SHRUBS	EACH	8	\$60.00	\$480.00	\$330.00	\$2,640.00	\$125.00	\$1,000.00	\$95.00	\$760.00
*NA	LARGE SHRUBS	EACH	15	\$75.00	\$1,125.00	\$550.00	\$8,250.00	\$540.00	\$8,100.00	\$370.00	\$5,550.00
*NA	PERENNIALS	EACH	169	\$20.00	\$3,380.00	\$27.50	\$4,647.50	\$16.00	\$2,704.00	\$22.00	\$3,718.00

\*INDICATES SPECIAL PROVISION

TOTAL = \$7,000,934.00

TOTAL = \$6,414,552.89

TOTAL = \$6,468,375.35

TOTAL = \$6,693,000.00